

BNPM/LTE/Workstation/1230/2020-21 Dated 25.03.2021	BANK NOTE PAPER MILL INDIA PRIVATE LIMITED WORKSTATION AT BNPM, MYSORE CORRIGENDUM NO. 1	SHEET 1 OF 1
---	---	--------------

CORRIGENDUM No. 1, DATED 05.04.2021

FOR

TENDER NO. BNPM/LTE/WORKSTATION/1230/2020-21 dated
25.03.2021

FOR

Supply and fixing of workstation.

PURCHASER: BANK NOTE PAPER MILL INDIA PRIVATE LIMITED

LOCATION : MYSORE, KARNATAKA



BNPM/LTE/Workstation/1230/2020-21 Dated 25.03.2021	BANK NOTE PAPER MILL INDIA PRIVATE LIMITED	SHEET 1 OF 1
	WORKSTATION AT BNPM, MYSORE CORRIGENDUM NO. 1	

1.0 SCOPE OF THIS CORRIGENDUM

1.1 This corrigendum issued to incorporate revision made in Tender for supply and installation of workstation. Details provided in this corrigendum shall override those mentioned in the Tender No. BNPM/LTE/Workstation/1230/2020-21 dated 25.03.2021.

1.2 Except for details mentioned herein, all other details contained in the Tender no. BNPM/LTE/Workstation/1230/2020-21 dated 25.03.2021, shall remain applicable and unchanged.

1.3 REVISION TO THE TENDER:

1.4 EMD details for the above tender

Initially EMD Amount: . 12,000/- (Rupees Twelve Thousand only)

Revised EMD Amount: ₹. 15, 000/- (Rupees Fifteen Thousand only)

1.5

“Revised Price Bid Format is attached”.

1.6 CLARIFICATIONS TO THE TENDER

Please refer: - Section: IX – Qualification /Eligibility Criteria (Tender Page No: 43)

The contents as mentioned in the tender under **Experience & Past Performance** is replaced with the below mentioned content:-

As Mentioned in Tender	May be read as
<p>The Bidder should have successfully completed the Interior works/Furniture supply during the last 5 (five) years ending 28.02.2021 as below;</p> <p>At least one work of Rs. 4.50 lakhs (Rs. Four Lakhs and Fifty Thousand only).</p> <p style="text-align: center;">Or</p> <p>Two works of Rs. 3.00 Lakhs (Rs. Three lakhs</p>	<p>The Bidder should have successfully completed the Interior works/Furniture supply during the last 5 (five) years ending 28.02.2021 as below</p> <p>At least one work of Rs. 5.80 lakhs (Rs. Five Lakhs and Eighty Thousand only).</p> <p style="text-align: center;">Or</p> <p>Two works of Rs. 3.60 Lakhs (Rs. Three lakhs Sixty Thousand only) each.</p> <p style="text-align: center;">Or</p>



BNPM/LTE/Workstation/123 0/2020-21 Dated 25.03.2021	BANK NOTE PAPER MILL INDIA PRIVATE LIMITED	SHEET 1 OF 1
	WORKSTATION AT BNPM, MYSORE CORRIGENDUM NO. 1	

<p>only) each.</p> <p style="text-align: center;">Or</p> <p>Three works of Rs. 2.25 Lakhs (Rs. Two lakh twenty five thousand only) each</p> <p>Note: Specialized agencies/civil contractors may apply to this tender provided they should have carried out Interior works as per above criteria</p>	<p>Three works of Rs. 2.90 Lakhs (Rs. Two lakh ninety thousand only) each under Experience & Past Performance Section - IX given in the tender.</p>
--	--

Please refer: - Section: XI- Price bid (Tender Page No: 42)

The contents as mentioned in the tender under price bid BOQ quantity may be read as mentioned below:

As Mentioned in Tender			May be read as		
Description	Unit	Quantity	Description	Unit	Quantity
Providing, Supplying and fixing of the modular workstations with the following specifications. Curvilinear Workstation - 1200mm x 1500mm X 600mm. Height of the partition panels to be at 1200 ht as per the details. Main frame :- 60mm thick slide based system finished with fabric above and laminate tile inside (below table top) and fabric outside. Above table top tiles are provided with one Ceramic Marker Board & one Fabric board per workstation. Return frame:- 60mm thick slide based system finished with fabric above and laminate tile inside (below table top) and fabric outside. Above table top tiles are provided with one Fabric Board & one Pinup board per workstation. Gable End:- Workstation top is supporting by	No	24	Providing, Supplying and fixing of the modular workstations with the following specifications. Curvilinear Workstation - 1200mm x 1500mm X 600mm. Height of the partition panels to be at 1200 ht as per the details. Main frame :- 60mm thick slide based system finished with fabric above and laminate tile inside (below table top) and fabric outside. Above table top tiles are provided with one Ceramic Marker Board & one Fabric board per workstation. Return frame:- 60mm thick slide based system finished with fabric above and laminate tile inside (below table top) and fabric outside. Above table top tiles are provided with one Fabric Board & one Pinup board per workstation.	No	30



BNPM/LTE/Workstation/123 0/2020-21 Dated 25.03.2021	BANK NOTE PAPER MILL INDIA PRIVATE LIMITED	SHEET 1 OF 1
	WORKSTATION AT BNPM, MYSORE CORRIGENDUM NO. 1	

<p>25mm thick PLPB with P.V.C edge finish as per approved colour. Gable end will have height adjustment leveller. Skirting:- To have metal powder coated skirting of manufacturers specs. Raceways:- Bi Layer Raceways are considered above table top or below the table for electrical and one more is at skirting level for data/ voice in Main Frame including electrical switch (8 module) and data point (2 module). Table top:- Table top made of 25mm thick PLPB table top. Table top will have 2mm edge banding profile on all exposed edges. Support - Work top is supported on 25mm thick PLPB Gable ends & necessary brackets, with fixed pedestal and keyboard tray & CPU trolley.</p> <p>Material should be of standard make.</p>			<p>Gable End:- Workstation top is supporting by 25mm thick PLPB with P.V.C edge finish as per approved colour. Gable end will have height adjustment leveller. Skirting:- To have metal powder coated skirting of manufacturers specs. Raceways:- Bi Layer Raceways are considered above table top or below the table for electrical and one more is at skirting level for data/ voice in Main Frame including electrical switch (8 module) and data point (2 module). Table top:- Table top made of 25mm thick PLPB table top. Table top will have 2mm edge banding profile on all exposed edges. Support - Work top is supported on 25mm thick PLPB Gable ends & necessary brackets, with fixed pedestal and keyboard tray & CPU trolley. Material should be of standard make</p>		
<p>Providing, Supplying and fixing of of mobile pedestal unit of size: 400mm(L) x 450mm(D) x 685(HT) mounted on heavy duty castors (4nos) & anti tilt roller. The unit is to be built of 18mm thick prelam board, carcass & fascia to have pvc edge banding & finished with matching laminate as worktop. To have two regular drawers and one filing unit. All drawers to be fitted with slider center locking facility. Stationary Separate will be provide for one small draw.</p> <p>Material should be of standard make.</p>	No	24	<p>Providing, Supplying and fixing of of mobile pedestal unit of size: 400mm(L) x 450mm(D) x 685(HT) mounted on heavy duty castors (4nos) & anti tilt roller. The unit is to be built of 18mm thick prelam board, carcass & fascia to have pvc edge banding & finished with matching laminate as worktop. To have two regular drawers and one filing unit. All drawers to be fitted with slider center locking facility. Stationary Separate will be provide for one small draw. Material should be of standard make.</p>	No	30



BNPM/LTE/Workstation/123 0/2020-21 Dated 25.03.2021	BANK NOTE PAPER MILL INDIA PRIVATE LIMITED	SHEET 1 OF 1
	WORKSTATION AT BNPM, MYSORE CORRIGENDUM NO. 1	

Closing date and time for receipt of tenders	23-04-2021 - 1100 Hours
Date and time of opening of Techno-commercial bid	23-04-2021 - 1130 Hours

